


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

PRATT County. Sec. 25 Twp. 26S Rge. 14 (X) (W)  
Location as "NE/CNW/SW" or footage from lines SE SW NE  
Lease Owner R. W. RINE DRILLING CO. AND BISHOP OIL COMPANY  
Lease Name STROBEL Well No. 1  
Office Address 320 CENTRAL BLDG., WICHITA, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed Nov. 25 1953  
Application for plugging filed Nov. 25 1953  
Application for plugging approved Nov. 25 1953  
Plugging commenced Nov. 25 1953  
Plugging completed Nov. 25 1953  
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production - 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well M. A. RIVES, PRATT, KANSAS  
Producing formation NONE Depth to top Bottom Total Depth of Well 4535 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	446	8-5/8"	446'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 240 feet to 300 feet for each plug set.

BOTTOM OF CEMENT PLUG AT 300' - 20 SACKS CEMENT - FILLED UP TO 240' - FILLED WITH MUD TO 40' - PLUG WITH 10 SACKS OF CEMENT FROM 40' TO 10'.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R. W. RINE DRILLING COMPANY  
Address 320 CENTRAL BUILDING, WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
JOHN H. WILSON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *John H. Wilson*  
320 CENTRAL BUILDING, WICHITA, KANSAS  
(Address)

SUBSCRIBED AND SWORN to before me this 28TH day of NOVEMBER, 1953

*Judy Giffen*  
Notary Public.

My commission expires JULY 31, 1957

24-7868-5 3-53-20M  
RECEIVED  
NOV 25 1953  
DIVISION  
12-1-53

PLUGGING  
FILE SEC 25 T 26 R 14W  
BOOK PAGE 145 LINE 29

15-151-10015-0000

SE-SW-NE  
SEC. 25-26-14W  
PRATT COUNTY, KANSAS

STROBLE WELL NO. 1

CONTRACTOR: THE R. W. RINE DRILLING COMPANY  
STARTED: 11-6-53 FINISHED: 11-25-53

		LOG	
SURFACE SOIL AND SAND	0	-	485
SHALE AND SHELLS	485	-	1985
SHALE AND LIME	1985	-	2435
LIME	2435	-	2605
LIME AND SHALE	2605	-	3395
CHALKY LIME	3395	-	3475
LIME AND SHALE	3475	-	3643
LIME, SHALE AND SAND	3643	-	3745
LIME AND SHALE	3745	-	3878
LIME	3878	-	3930
SHALE AND LIME	3930	-	3947
LIME	3947	-	3963
LIME AND SHALE	3963	-	4015
LIME	4015	-	4085
LIME AND SHALE	4085	-	4253
LIME	4253	-	4278
LIME AND CHERT	4278	-	4320
LIME, SHALE AND CHERT	4320	-	4479
LIME	4479	-	4512
LIME AND SHALE	4512	-	4535

8-5/8" @ 436' W/300 SX  
 SYFO @ 1765'-3/4"  
 SYFO @ 2227'-1/2"  
 SYFO @ 3084'-3/4", 3387'-1/2"  
 SYFO @ 3900'-1/2"

TOTAL DEPTH- PLUGGED 11-25-53

I, R. M. GREEN, DO HEREBY CERTIFY THAT THE ABOVE IS A TRUE AND ACCURATE LOG OF THE STROBLE WELL NO. 1, LOCATED SE-SW-NE, SEC. 25-26-14W, PRATT COUNTY, KANSAS.

*Recd.  
12-1-53*

*R. M. Green*  
 ASSISTANT SECRETARY

SUBSCRIBED TO AND SWORN BEFORE ME THIS 30 DAY OF NOVEMBER, 1953.

*Luddy E. Loper*  
 NOTARY PUBLIC

MY COMMISSION EXPIRES 7-31-57

**PLUGGING**  
 FILE SEC 25 T 26 R 14W  
 BOOK PAGE 145 LINE 29