

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

**Well Plugging Record**  
**K.A.R. -82-3-117**

API NUMBER 15-151-221540000  
LEASE NAME Long  
WELL NUMBER No. 5

TYPE OR PRINT  
NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

1595 Ft. from South Line of Section  
1815 Ft. from West Line of Section

LEASE OPERATOR Kenneth S. White SPOT LOCATION 55' S. and 165' E. of C Sw Ne Sw  
ADDRESS 200 E. First, Suite 405 Section 5 Township 26s Range 11w  
CITY, STATE, ZIP Wichita, Kansas 67202 County Pratt  
PHONE # 316-263-4007 Date Well Completed July 24, 1997  
Character of Well Dry and Abandoned Date Plugging Commenced July 24, 1997  
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed July 24, 1997

The plugging proposal was approved on July 22, 1997 at 8:30 am (date)  
by Gary Winters (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes  
Producing Formation(s) D&A Depth to Top Bottom T.D. 4275

Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS**

**CASING RECORD**

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	127	and		
Redbeds	Shale/Siltstone	127	265	10-3/4"	249.54	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet each set.

Heavy mud from RTD to 700', then 50 sacks. Heavy mud to 300' then 90 sacks.  
Heavy mud to 40' then 20 sacks. Plugged rathole with 15 sx and mousehole with 10 sx.  
Started plugging at 12:45 pm. Plug down at 2.00 pm on 7-24-97 by Allied using  
60/40 Poz, 6% Gel. Ticket # 8286.

7-29-97

Name of Plugging Contractor Sterling Drilling Company  
Licence No. 5142  
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124  
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kenneth S. White (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.

Steve E. McClain, Agent (Employee of Operator or (Operator) of above described well, being first  
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of  
the above described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
(Steve E. McClain, President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 25th day of July, 19 97



[Signature]  
(Notary, Public)

RECEIVED  
KANSAS CORP COM 1  
1997 JUL 29 A 1:20

My Commission Expires: \_\_\_\_\_

**Sterling Drilling Company, Rig #4**

Box 1006, Pratt, Kansas 67124-1006  
Office Phone (316) 672-9508, Fax 672-9509

**SAMPLE LOG****Long No. 5**

**LOCATION:** 55' S. and 165' E. of C Sw Ne Sw      Section 5    T 26s    R 11w  
**API:** 15-151-221540000      Pratt County, Kansas

**OWNER:** Kenneth S. White  
**CONTRACTOR:** Sterling Drilling Company, Rig #4

**COMMENCED:** 17-Jul-97  
**COMPLETED:** 24-Jul-97

**TOTAL DEPTH:**    **DRILLER**    4275    FEET  
                          **LOGGER**    4275    FEET

**Ground Elevation:** 1851  
**KB Elevation:** 1860

**LOG**

0 -            127 FEET      Top Soil and Sand  
127 -        669 FEET      Redbeds  
669 -        690 FEET      Anhydrite  
690 -        4275 FEET     Limestone, Shale and Chert

**CASING RECORDS**

Spud @ 8:30 am on 7-17-97. Drilled 14-3/4" hole to 265'. Ran 6 joints of 10-3/4" surface casing 249.54' set at 261' KB. Cemented with 225 sacks 60/40 Poz, 2% Gel, 3% CC. Plug down at 4:00 pm on 7-17-97 by Allied. Good returns. Ticket # 7189.

Received plugging orders at 8:30 am on 7-22-97 from Gary Winters.  
Plugged well with:    Heavy mud from RTD to 700', then 50 sacks,  
                                  Heavy mud to 300', then 90 sacks,  
                                  Heavy mud to 40' then 20 sacks,  
                                  Plugged rathole with 15 sacks and mousehole with 10 sacks.

Started plugging at 12:45 pm. Plug down at 2.00 pm on 7-24-97 by Allied using 60/40 Poz, 6% Gel. Ticket # 8286.

7-29-97

**DEVIATION SURVEYS**

1/4 degree(s) at    265    feet  
1 1/2 degree(s) at    4275    feet

RECEIVED  
KANSAS CORP CO:TM  
1997 JUL 29 A 1:20