

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

#1
API NUMBER 15,151-20048,00-0

LEASE NAME Schlenz #2

WELL NUMBER _____

SPOT LOCATION NW SW

SEC. 6 TWP. 26S RGE. 11 (E) or (W)

COUNTY Pratt

Date Well Completed _____

Plugging Commenced 8/26/85

Plugging Completed 8/29/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Fina Oil & Chemical

ADDRESS 1601 NW Expressway, Suite 900
Box 2159, Dallas, Tx. 75221

Oklahoma City, Oklahoma 73118

PHONE # (214) 750-2400 OPERATORS LICENSE NO. 5692

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4151'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				13"	289'	none
				9 5/8"	950'	none
				4 1/2"	4151'	1982'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Set rock bridge @ 3670' & ran 4 sacks cement. Shot pipe at 2500', & 1982'.

Pulled 67 joints of pipe. Plugged well with 3 hulls, 10 gel, 50 cement, 6 gel, 1 hull, & 150 sacks 60/40 poz 6% gel.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524 9-6-85

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) Mike Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 4th day of September, 1985

My Commission expires:



Irene Hoover
Notary Public