

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Pratt County, Sec. 27 Twp. 26 Rge. 13 (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SW SE

Lease Owner R. W. Rine Drilling Company

Lease Name Hoener Well No. A-1

Office Address P. O. Box 452 Pratt, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 2-26-65 19


Plugging completed 3-4-65 19

Reason for abandonment of well or producing formation

Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie V. Elving

Producing formation Depth to top Bottom Total Depth of Well 3930 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	835	None
				5 1/2	None	3217

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cleaned out cellar. Working pipe.

Sanded to 3790'. Dumped 5 sacks of cement. Shot pipe at 3190'.  
Circulating. Spotted 60 hbl of oil.

Working pipe. Pulling pipe.

Pulling pipe. Plugging well. Bailed to 300' rock bridge. Dumped  
25 sacks of cement. Filled hole and rock bridge. Capped well with  
10 sacks of cement.

3-10-65

RECEIVED  
STATE CORPORATION COMMISSION

MAR 10 1965

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J. O. Forbes

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J O Forbes

P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 8 day of March, 19 65

[Signature] Notary Public.

My commission expires May 27, 1965

WELL NO. 1

SW SW SW  
Section 27-26S-13W  
Pratt County, Kansas

Drilled for: Cities Service and Rine Drilling  
Drilled By: Beardmore Drilling Company, Inc.

Casing Record:

8-5/8" 835' w/400 Sacks

Drilling Commenced: July 25, 1951  
Drilling Completed: August 15, 1951

Elevation:

<u>FORMATION</u>	<u>DEPTH</u>
Clay	45
Sand	100
Sand - Gravel	175
Shale - Shells	828
Anhydrite	835
Shale- Shells	1710
Shale - Lime	1895
Lime	2000
Lime Broken	2170
Lime	2240
Sandy Lime	2270
Lime	2310
Lime - Shale	2850
Shale - Lime	3010
Lime - Shale	3410
Lime	3495
Lime Broken	3595
Lime - Shale	3755
Lime	3865
Lime - Shale Bks.	3924
Lime	4200
Cherty Lime	4210
Lime Mississippi	4245
Lime	4364
Lime - Shale	4454
Lime	4490 T.D.

2-10-65

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 10 1965  
CONSERVATION DIVISION  
Wichita, Kansas

Tops:

DST #1 - 3806-3826 - 50' Mud  
DST #2 - 3939 - 125' oil out mud  
DST #3 - 3991 - Approx. 60' mud

DST #4 - 4184-4210 1-1/2 million ft. gas  
DST #5 - 4305 Flowed oil in 25 min.  
DST #6 - 4454 - 27' anchor

STATE OF KANSAS

COUNTY OF SEDGWICK

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above described, to the best of my knowledge and belief.

*Richard Beardmore*

Subscribed and sworn to before me this 22nd day of August, 1951.

*Annette A. Kennally*  
Notary Public

My Commission Expires: January 19, 1955