

TATE OF KANSAS
TATE CORPORATION COMMISSION
30 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

15-151-10809-00-00
API NUMBER Drilled 1947

LEASE NAME Chance

WELL NUMBER 1-A

660 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 32 TWP. 26 RGE. 13W(E) or (W)

COUNTY Pratt

Date Well Completed _____

Plugging Commenced 3-9-01

Plugging Completed 3-19-01

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR RAMA OPERATING CO., INC.

ADDRESS P.O. Box 159 Stafford, Kansas 67578

PHONE (316) 234-5191 OPERATORS LICENSE NO. 3911

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom DET.D. 4463'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION
MAR 30 2001
3-30-01

Formation	Content	From	To	Size	Put In	Pulled out
				10-3/4"	827'	None
				7"	4448'	2210'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from feet to _____ feet each, or plugged off bottom with sand to 2900' and 7 sks. cement, shot pipe 2600', 2400' and 2210'. Pulled up to 850', pumped 8 sks. gel, 75 sks. cement, and 7 sks. gel, pulled up to 400', pumped 30 sks. cement, pulled up to 40' and circulated 45 sks. cement to surface. 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rama Operating Co., Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 28th day of March, 2001

[Signature]
Notary Public

My Commission Expires: _____



Form CP
Revised 05-