


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plat

pratt County, Sec. 32 Twp. 26 Rge. 13 (E) (W) X  
Location as "NE/CNW/SW" or footage from lines. C W/2 SE NE  
Lease Owner Earl Allen Oil Co.  
Lease Name Tregallas Well No. #6  
Office Address Box 339 Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 12-13-74 19  
Application for plugging approved 19  
Plugging commenced 1-8-75 19  
Plugging completed 1-13-75 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein  
Producing formation Depth to top Bottom Total Depth of Well 4290'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	4279'	2849.20'
				9 5/8"	850'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 4250'. Mixed and ran 5 sacks cement thru dump bailer.  
Mudded hole to 280' - set 15' rock bridge. Filled hole with 4 1/2 yards ready-mix concrete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co.  
Address Box 364 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.

Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer, Inc.

Box 364 Great Bend, Kansas

(Address)

16 day of January, 1975

Sidney D. Miller  
Notary Public.



RECEIVED  
STATE CORPORATION COMMISSION

JAN 17 1975

1-17-75

CONSERVATION DIVISION  
Wichita, Kansas

# WELL LOG

15-151-10868-0000

COMPANY Continental Oil Company

SEC. 32 T. 26 R. 13N

FARM TREGALLAS NO. 6


LOC. C W/2 SE NE

TOTAL DEPTH 4290

COUNTY Pratt County, Kansas

COMM. April 4, 1954. COMP. April 16, 1954.

CONTRACTOR Carvey Drilling Company



CASING 9-5/8" @ 850' w/100 sax.  
5 1/2" @ 4279' w/200 sax.

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

375	Shale & Shells
710	Red Bed
825	Red Bed & Shale
841	Sand
850	Anhydrite
865	Anhydrite
1900	Shale & Shells
2280	Lime
2425	Lime & Shale
2680	Lime
3300	Lime & Shale
4200	Lime
4232	Cherty Lime
4290	Lime

R.T.D. 4290'

RECEIVED  
STATE CORPORATION COMMISSION

DEC 16 1974

CONSERVATION DIVISION  
Wichita, Kansas

12-16-74

Copy to:  
LED ✓  
SAC  
Jkt

State of KANSAS }  
County of SEDGWICK } SS:

I, W. W. Fisher of Carvey Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the TREGALLAS #6 well.

W. W. Fisher

Subscribed and sworn to before me this 21st day of April 19 54

My Commission Expires: October 13, 1954

Sharon Menden  
NOTARY PUBLIC