

STATE OF KANSAS  
CORPORATION COMMISSION  
S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

API NUMBER 15-151-10814-00-00

LEASE NAME Chance

WELL NUMBER 6

1650 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 32 TWP. 26 RGE. 13W (E) or (W)

COUNTY Pratt

Date Well Completed 9-1-53

Plugging Commenced 7-31-02

Plugging Completed 8-2-02

BASE OPERATOR RAMA OPERATING CO., INC.

ADDRESS P.O. Box 159 Stafford, Kansas 67578

PHONE (620) 234-5191 OPERATORS LICENSE NO. 3911

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

A plugging proposal was approved on \_\_\_\_\_ (date)

Steve Pfeifer (KCC District Agent's Name).

ACO-filled? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4475'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10-3/4"	847'	None
				7"	4473'	1800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material is used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet surface. Plugged off bottom with sand to 4600' and 7 sacks cement. Shot pipe @1800', pulled up to 870'. pumped 15 sacks gel, 75 sacks cement and 200# hulls, pulled up to 400', pumped 50 sacks cement and 200# hulls, pulled up to 40' and circulated 55 sacks cement to surface. Plugging Complete. 60/40 pos. 6% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rama Operating Co., Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed therewith are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 14th day of August, 2002

My Commission Expires:

