

STATE OF KANSAS STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 212 No. Market Wichita, Kansas

Pratt County. Sec. 33 Twp. 26 Rge. 13 (E) X (W)

Location as "NE/CNW/SW" or footage from lines SE NE NW

Lease Owner Specter Pipe & Supply, Inc.

Lease Name Taylor Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 1-29-49 19

Application for plugging filed Nov. 16, 1967 19

Application for plugging approved Nov. 17, 1967 19


Plugging commenced February 6, 19 68

Plugging completed February 6, 19 68

Reason for abandonment of well or producing formation failure to produce profitably

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well Archie Elving Producing formation Arbuckle Depth to top 4416 Bottom 4420 ft Total Depth of Well 4420 Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Contains data for 8 5/8" OD and 5 1/2" OD casings.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

plugged off bottom with 5 sacks cement; set 10' rock bridge at 400ft. set 25 sacks cement; topped with 10 sacks cement.

RECEIVED STATE CORPORATION COMMISSION FEB 23 1968 CONSERVATION DIVISION Wichita, Kansas

Name of Plugging Contractor Lynch Casing Pulling Co. Address Route 4 Gt. Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss. Specter Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 20th day of February, 1968. [Signature] Notary Public. My commission expires May 21, 1971



WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

15-151-10830-0000  
COPY

Company, SUNRAY OIL  
Farm - Taylor

No. 1

SEC. 33

T. 26

R. 13W

SE. NE NW

Total Depth: 4420'

Comm. 1-29-49

Comp. 2-18-49


Shot or Treated.

Contractor, R. W. Rins Drilling

Issued. 4-16-49

County, Pratt

KANSAS



Elevation. \_\_\_\_\_

Production. Pmp 75 bbl oil

CASING:

8 5/8" 810' cem w/500 sx  
cem w/275 sx  
5 1/2" 4421' cem w/150 sx

Figures Indicate Bottom of Formations.

sand, clay	210
shale, shells	285
red bed	410
red bed shale, shells	525
red bed, shells	775
shale, shells	810
re-cemented	
shale, shells	2185
salt, shale, shells	1575
shale, shells	1870
lime, shale	2380
shale	2405
lime, shale	2715
shale, shells	2790
lime, shale	2935
shale	3000
lime, shale	3760
lime	4020
lime, shale	4173
shale	4195
shale, chert	4216
lime, chert	4245
lime, shale	4267
chert, shale	4320
Coring #1	4327
Coring #2	4339
sand & shale	4373
shale	4419
Core #3	4420
lime ?	4422
Total depth	

Tops:

Lansing	3770
Conglomerate	4194
Viola	4222
Simpson	4306
Arbuckle	4416

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 20 1967  
11-20-67  
CONSERVATION DIVISION  
Wichita, Kansas