


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Pratt County, Sec. 33 Twp. 26S Rge. 13W (E) (W)
Location as "NE/CNW/SW" or footage from lines. NE SE NW
Lease Owner Dundee Oil & Supply Inc.
Lease Name Strait Well No. 1
Office Address P.O. Box 2391, Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 19____
Application for plugging filed July 1973 19____
Application for plugging approved July 1973 19____
Plugging commenced 8-25-1973 19____
Plugging completed 8-31-1973 19____
Reason for abandonment of well or producing formation Not Commercial
If a producing well is abandoned, date of last production June 1973 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	795'	none
				5 1/2"	4418'	2302'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

8-25-1973 Plugged off bottom. Dumped sand to 4000'. Mixed and dumped 5 sx cement.
8-31-1973 Plugged off top. Set 10' rock bridge in 8-5/8" surface casing from 250'. Filled 8-5/8" surface casing from 250' to base of cellar with 3000 lb. P.S.I. ready mix concrete.

10-26-73

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1973
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor RUSS CASING PULLING, INC.
Address P.O. Box 1082, Great Bend, Kansas

STATE OF Oklahoma, COUNTY OF Tulsa, SS.
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Michael O. Hender

SUBSCRIBED AND SWORN to before me this 25 day of Oct, 1973

My commission expires Jan-25, 1973
Notary Public.

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
 412 Union National Bldg. Wichita, Kansas


15-151-10837-0000

Company - DEEP ROCK OIL COMPANY & RINE DRLG. CO.
 Farm - Strait No. 1

SEC. 33 T. 26 R. 13W
 NE SE NW

Total Depth. 4426'
 Comm. 12-5-48 Comp. 1-9-49
 Shot or Treated.
 Contractor.
 Issued. 2-19-49

County. Pratt
 KANSAS



CASING:
 8-5/8" 795' 5-1/2" 4418'

Elevation. 1952
 Production. Pot. 75 BOPD

Figures Indicate Bottom of Formations.

top soil & sand	40
red bed & sand	660
shale & shells	1820
shale	2010
lime	2140
lime & shale	2290
lime	2707
lime, shale & shells	2835
lime & shale	3041
shale & shells	3275
shale	3360
lime & shells	3510
lime	3860
lime & shale	3910
lime	3935
lime shells	3990
lime	4030
lime hrd	4060
lime	4105
lime hrd	4146
lime	4199
chert	4258
shale	4283
lime	4287
chert	4350
sand & shale	4397
lime	4426
Total Depth	
Tops:	
Kansas City	3778
Simpson	4327
Arbuckle	4418

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 23 1973
 CONSERVATION DIVISION
 Wichita, Kansas

7-23-73