

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 33 Twp. 26S Rge. (E) 13(W)

Location as "NE/CNW%SW%" or footage from lines NW SE NW

Lease Owner General American Oil Company of Texas

Lease Name Strait Well No. 5

Office Address P.O. Box 1358, Seminole, Oklahoma 74868

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 19

Application for plugging filed July 18 1968

Application for plugging approved 19

Plugging commenced July 20 1968

Plugging completed July 26 1968

Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren

Producing formation Depth to top Bottom Total Depth of Well 4429 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	870'	8 5/8"	870'	none
		0	4464'	5 1/2"	4464'	2090.64

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Push plug to 4280', set 10' rock bridge and dumped 5 sacks cement.

Pushed plug to 300'; set 10' rock bridge. Bailed down hole and dumped 25 sacks cement. Filled hole with mud to 40' and capped hole with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
AUG 8 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pipe Pullers, Inc.
Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
E. L. Schonhoff

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. L. Schonhoff
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of August, 1968

My commission expires Feb. 10, 1971

George A. Meyer
Notary Public.

DRILLER'S LOG - STRAIT WELL NO. 5

Surface Clay	0	40
Sandy Clay	40	70
Sand	70	170
Shale and Shells	170	230
Red Bed	230	245
Red Bed & Shale	245	675
Red Bed	675	830
Anhydrite	830	855
Shale	855	875
Shale & Shells	875	1370
Shale, Salt & Lime	1370	1875
Shale	1875	2020
Sandy Lime	2020	2055
Lime and Shale	2055	2490
Shale	2490	2510
Lime and Shale	2510	2895
Sandy Lime & Shale	2895	3020
Lime and Shale	3020	3700
Lime	3700	4173
Lime and Chert	4173	4195
Lime	4195	4261
Shale	4261	4265
Shale and Chert	4265	4300
Chert	4300	4314
Shale and Chert	4314	4355
Lime	4355	4365
Lime and Shale	4365	4415
Lime	4415	4465 TD

RECEIVED
STATE CORPORATION COMMISSION
JUL 19 1968
CONSERVATION DIVISION
Wichita, Kansas