


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
30% Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Pratt County, Sec. 33 Twp. 26 Rge. 13 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SW NW NW  
Lease Owner Oklahoma Fracturing Service  
Lease Name Taylor Well No. #6  
Office Address 630 United Founders Life Tower, Okla. City, OK.  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed August 1974  
Application for plugging approved August 1974  
Plugging commenced August 13 1974  
Plugging completed August 27 1974  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	882	None
				5 1/2"	4479	2987

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

8-13-74 Plugged off bottom. Dumped sand to 4000'. Mixed and dumped 5 sx of cement.  
8-27-74 Plugged off top. Sun Oil Well Cementing Co. mixed and pumped down 8 5/8" surface casing, 2 sx of hulle, 10 sx of gel and 100 sx of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 12 1974  
9-12-74  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor RUSS CASING PULLING, INC.  
Address P. O. Box 1082, Great Bend, Kansas 67530

STATE OF Okla COUNTY OF Okla

\_\_\_\_\_, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) Oklahoma Fracturing Service, Inc.

Subscribed and Sworn to before me this 11<sup>th</sup> day of September, 1974  
(Address) 630 United Founders Tower, Okla City, Okla 73112

My commission expires April 9, 1977  
\_\_\_\_\_  
Notary Public.



DRILLER'S LOG

SUNRAY OIL CORPORATION  
 No. 6 Taylor  
 SW NW NW Section 33-265-13W  
 Pratt County, Kansas

FROM	TO	
0	220	Clay and Sand
220	640	Red Bed, Shale and Shells
640	975	Red Shale and Shells
0	975	Reaming
975	1245	Shale and Shells
1245	1580	Shale, Shells and Salt
1580	1830	Shale and Shells
1830	2055	Lime
2055	2165	Lime and Shale
2165	2290	Lime
2290	2495	Lime and Shale
2495	2690	Shale
2690	2955	Lime and Shale
2955	3040	Shale
3040	3090	Lime and Shale
3090	3260	Shale
3260	3779	Shale and Lime
3779	4115	Lime
4115	4155	Lime and Shale
4155	4200	Lime
4200	4270	Chert and Lime
4270	4310	Shale, Lime and Chert
4310	4350	Chert
4350	4400	Shale and Lime
4400	4421	Shale and Chert
4421	4482	Lime
4482		Total Depth

COMMENCED: 2-6-52

COMPLETED: 2-23-52

CASING RECORDS:

8-5/8" surface casing set at 681.71' with 650 sacks cement, 4% gel, 2% floccul

5-1/2" casing set at 4482' with 200 sacks cement and 4% gel

RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG 14 1954  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 )  
 COUNTY OF SEDGWICK )

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Sunray No. 6 Taylor located SW NW NW Section 33-265-13W, Pratt County, Kansas.

ANSCHUTZ DRILLING COMPANY

By: *Leon L. Mehler*  
 Leon L. Mehler

Subscribed and sworn to before me this 26th day of February, 1952.

My Commission Expires: May 24, 1952

*Wilma L. Shifman*  
 Notary Public