

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas


OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Pratt County. Sec. 34 Twp. 26S Rge. ~~13W~~ 13W (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. SE $\frac{1}{4}$
Lease Owner. Olson Drilling Co.
Lease Name. C.F. Briggeman Well No. 1
Office Address. P.O. Drawer 2680, Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole). Dry Hole
Date well completed. Sept. 11, 1949 19
Application for plugging filed. Verbal Sept. 10, 1949 19
Application for plugging approved. By C.D. Stough Sept. 10, 1949 19
Plugging commenced. Sept. 11, 1949 19
Plugging completed. Sept. 11, 1949 19
Reason for abandonment of well or producing formation. Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production. 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well. C.D. Stough, Great Bend, Kansas
Producing formation. Depth to top. Bottom. Total Depth of Well. 4451 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle Lime	Dry	4390	4417	8 5/8"	786'	None - Cemented (surface pipe)

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Filled hole to 200 ft. with heavy mud.
Set bridge plug at 200 ft. Cemented with
15 sacksthrough drill pipe. Filled with
heavy mud to 30 ft. from bottom of cellar.
Set bridge plug and 10 sacks of cement to
bottom of cellar.

RECEIVED
SEP 15 1949
9-15-49
ST.
CORPORATION
DIVISION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. Olson Drilling Co.
Address. Burrton, Kansas.


STATE OF Kansas, COUNTY OF Harvey, ss.
J. L. Mc Mann (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

(Signature) J. L. Mc Mann
(Address) _____

SUBSCRIBED AND SWORN to before me this 14th day of September, 1949

My commission expires July 27, 1952

Notary Public.



- 6
- 45 Soil
- 140 Sand
- 245 Sand
- 540 Red beds, shale & shells
- 571 Red shale & shells
- 620 Red shale & shells
- 785 Anhydrate
- 811 Lime
- 1050 Red bed, shale & shells
- 1370 Shale & shells
- 1405 Shale & salt
- 1660 salt shale, shale
- 1800 Lime & Shale
- 1955 Anhydrate & Shale
- 2040 Lime
- 2155 Lime
- 2180 Lime
- 2245 Lime
- 2560 Lime
- 2605 Lime & shale
- 2920 Shale & lime& shells
- 2975 Lime & shale
- 3355 Lime
- 3453 Lime
- 3632 Shale
- 3642 Lime
- 3670 Sand
- 3715 Shale
- 3757 Shale
- 3772 Lime
- 4065 Lime & shale
- 4100 Lime
- 4133 Lime & Shale
- 4140 Lime
- 4144 Shale
- 4156 Lime & shale
- 4175 Misc. lime
- 4197 Lime
- 4215 Chert & lime
- 4234 Sandy shale
- 4247 Sandy lime
- 4279 Chirty lime
- 4299 Sandy lime
- 4375 Sandy shale
- 4390 Dolomite
- 4400 Dolomite & Arbuckle lime
- 4417 Lime
- 4451 Lime
- 4451 Total Dept.

9-15-49

RECEIVED
PLUGGING
 FILE SEC 34 T16 R13W
 BOOK PAGE 114 LINE 194

Olson Drilling Co.
 C.F. Briggeman
 SE 1/4 Sec. 34 T16 R13W
 Pratt County, Kansas
 Commenced 8/13/49
 Completed 9/11/49
 Dry Hole

J. H. McManis
 Signed before me this 14th day of Sept. 1949
 A.C. [unclear] [unclear] [unclear]
 Harry County, Kansas