


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Pratt County, Sec. 35 Twp. 26 Rge. 13 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
NW NE SE  
Lease Owner K & E Drilling, Inc.  
Lease Name John Brown #1 Well No.  
Office Address Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plot

Date Well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 7/22/80 19  
Plugging completed 7/30/80 19  
Reason for abandonment of well or producing formation  
depleted  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes  
Owen

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 4354  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE-	PUT IN	PULLED OUT
				8-5/8	479	none
				5 1/2"	4352	3634'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded to 3750' and ran 5 sacks cement. Shot pipe at 3610', pulled 112 joints. Squeezed hole with 15sacks gel, 8 sacks hulls, 10 sacs gel. Released plug and displaced with 150 sacks 50-50 poz, 4% gel, 3% cc.

PLUGGING COMPLETE.

8-5-80  
RECEIVED  
STATE CORPORATION COMMISSION  
AUG - 5 1980  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of July, 19 80

Margaret Melcher  
Notary Public.

My commission expires



DRILLER'S LOG

John W. McKnab  
John Brown #1  
NW NE SE 35-26-13W  
Pratt County, Kansas

<u>TO</u>	<u>FROM</u>	
0	515	Sand, Shale & Red Roch
515	860	Sand & Red Bed
860	1190	Shale & Shells
1190	1200	Shale & Shells
1200	1240	Shale & Red Bed
1240	1655	Shale & Shells
1655	2070	Shale & Lime
2070	2175	Lime
2175	2420	Lime & Shale
2420	3690	Shale & Lime
3690	3748	Shale & Lime
3748	4240	Lime
4240	4285	Sand
4285	4333	Shale & Lime
4333	4354	Lime
	4354	ROTARY TOTAL DEPTH

COMMENCED: 2-20-55  
COMPLETED: 3-9-55

CASING RECORD

Set 479' of 8 5/8" surface casing with 300 sacks of cement and 2 c.c.

Set 4352' of 5 1/2" casing with 150 sacks of cement.

NOTE-----at 4354 the drill pipe was strapped on the rack and tallied 4357. Thus 4354 = 4357. All sample determinations should be moved 3 ft. down the hole. This adjustment is felt to be reliable since the Schlumberger recorded most tops and porous zones one to three feet deeper than sample determinations. No correction has been made in this report simply to avoid confusion with data phoned in and already recorded.

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

6-11-80

I hereby affirm that the above and foregoing is a true and correct copy of the log of the John Brown #1 located in the NW NE SE of Section 35, Township 26 South, Range 13 West, Pratt County, Kansas.

MC KNAB DRILLING, INC.

*Don Gardner*  
Don Gardner

RECEIVED  
JUN 11 1955  
Pratt County, Kansas

Subscribed and sworn to before me this 16th day of March 1955

*Helen L. Long*  
Notary Public

My Commission Expires November 21, 1956