


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Pratt County, Sec. 35 Twp. 26S Rge. 13 (W) W (W)
Location as "NE/CNW/SW" or footage from lines NE NW NW
Lease Owner The R. W. Rine Drilling Company
Lease Name Hoener "B" Well No. 5 (cave-in)
Office Address 320 Central Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Not completed
Date well completed Cave-In - February 29 1956
Application for plugging filed Letter of 3/9/56, followed by application 4/20 1956
Application for plugging approved April 23 1956
Plugging commenced April 24 1956
Plugging completed June 15 1956
Reason for abandonment of well or producing formation Cave-in at approximate total depth of 807'.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 8, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 807 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface soil, sand and clay - water sand					No casing run	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Approximate total depth of hole drilled - 807'. Approximate total depth of cave-in - 15'.

April 24, 1956 - Commenced plugging by hauling in and dumping in hole 6 truck loads of large cement blocks (approximate size 1' x 4' x 3'), followed with 6 yards oversize gravel. This was allowed to settle for 50 days.

June 13, 1956 - Cemented over top of rock and gravel with 18 yards of ready mix cement (mixed @ 5 sacks cement w/ 3100 lbs. sand per yard). Cement allowed to set up.

June 15, 1956 - Completed operation by filling in over cement with fill dirt, packed and leveled.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R. W. Rine Drilling Company
Address 320 Central Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

E. H. SLOYER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. H. Sloyer

320 Central Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of June 1956

Loren E. Lake Notary Public.

My commission expires June 14, 1958.

24-7366-5 3-53-20M

PLUGGING
FILE SEC 35 T. 26 R. 13w
BOOK PAGE 55 LINE 32

STATE CORP
JUN 19 1956 6-19-56
CONSERVATION DIVISION
Wichita, Kansas

15-151-19112-0000

HOENER "B" WELL NO. 5 (Cave-In)

NE NW NW
Sec. 35-26S-13W
Pratt County, Kansas

CONTRACTOR: THE R. W. RINE DRILLING COMPANY

STARTED: February 27, 1956

COMPLETED: March 1, 1956

L O G

Sand	0'	260'
Red Bed	260'	310'
Red Bed, Sand and Shale	310'	744'
Red Bed and Sand	744'	807'

Syfo @ 550' 0"

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

I, R. M. GREEN, do hereby certify that the above is a true and accurate log of the Hoener "B" Well No. 5 (cave-in), located in the NE NW NW of Sec. 35-26S-13W, Pratt County, Kansas.


Assistant Secretary-Treasurer

Subscribed and sworn to before me this 18th day of June, 1956.


Notary Public

(My commission expires June 14, 1958.)

PLUGGING	
FILE SEC. 35 T. 26 R. 13W	
BOOK PAGE 55 LINE 32	

FILED 6-19-56
JUN 19 1956
CONSERVATION DIVISION
Wichita, Kansas