

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-151-221620000
LEASE NAME Reichardt
WELL NUMBER #1

TYPE OR PRINT

5-6-98

NOTICE: Fill out completely and return **RECEIVED** 1040 Ft. from South Line of Section
to Cons. Div. office within 30 days; **KANSAS CORP COMM** 1700 Ft. from East Line of Section

LEASE OPERATOR Bankoff Oil Company **1998 MAY -6** **SPOT LOCATION** 50'N & 50'W of NE SW SE
ADDRESS P.O. Box 700657 Section 1 Township 26s Range 14w
CITY, STATE, ZIP Tulsa, Oklahoma 74170-0657 County Pratt
PHONE # 918-742-0450 Date Well Completed May 4, 1997 **98**
Character of Well Dry and Abandoned Date Plugging Commenced May 4, 1997 **98**
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed May 4, 1997 **98**

The plugging proposal was approved on May 1, 1998 at 8:15 am (date)
by Steve Middleton (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 4300

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	260	and		
Redbeds	Shale	260	300	8-5/8"	281.09	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged well as follows:

Heavy mud to 900', then 40 sacks. Heavy mud to 320', then 40 sacks. Heavy mud to 40', then 10 sacks. Plugged rathole with 15 sacks and mousehole with 10 sacks. Using 60/40 Poz, 6% Gel. Plug down at 1:30 on 5-4-98 by Allied. Ticket # 2628.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bankoff Oil Company (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Steve E. McClain, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Steve E. McClain, President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 5th day of May, 19 98



[Signature]
(Notary Public)

My Commission Expires: _____

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (316) 672-9508, Fax 672-9509

RECEIVED
AS CORP COMM

1998 MAY -6 12:11

SAMPLE LOG

Reichardt #1

LOCATION: 50'N & 50'W of NE SW SE Section 1 T 26s R 14w
API: 15-151-221620000 Pratt County, Kansas

OWNER: Bankoff Oil Company
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 28-Apr-98
COMPLETED: 05-May-98

TOTAL DEPTH: **DRILLER** 4,300 FEET
LOGGER Not logged FEET

Ground Elevation: 1964
KB Elevation: 1973

LOG

0 -	260 FEET	Top Soil and Sand
260 -	855 FEET	Shale and redbeds
855 -	887 FEET	Anhydrite
887 -	4300 FEET	Limestone, Shale and Chert.

CASING RECORDS

Spud @ 9:45 am on 04-28-98. Drilled 12-1/4" hole to 300'. Ran 7 joints of 8-5/8" surface casing 281.09' set at 293' KB. Cemented with 235 sacks 60/40 Poz, 2% Gel, 3% CC. Plug down at 3:15 pm on 04-28-98 by Allied. Good returns. Ticket # 2619.

Received plugging orders at 8:15 am on 5-1-98 from Steve Middleton. Plugged well as follows:

Heavy mud to 900', then 40 sacks. Heavy mud to 320', then 40 sacks. Heavy mud to 40', then 10 sacks. Plugged rathole with 15 sacks and mousehole with 10 sacks. Using 60/40 Poz, 6% Gel. Plug down at 1:30 on 5-4-98 by Allied. Ticket # 2628.

DEVIATION SURVEYS

1/2	degree(s) at	300	feet
1	degree(s) at	4300	feet