

Orig - State Corp. Comm.  
 Copy - B. A. Conner - 357 FPB  
 Copy - Mary Crump - Okla. City  
 Copy - Well File

15-151-20908-00-00

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Bldg.  
 Wichita, Kansas 67202

Form CP-4  
 Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Pratt SEC. 2 TWP. 26S RGE. 14 E/W  
 Location as in quarters or footage from lines:  
990' FSL & 990' FWL of SW/4


Lease Owner Phillips Petroleum Company  
 Lease Name Henderson-B #2 Well No. 2  
 Office Address Box 287, Great Bend, Kansas 67530  
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
 Date Well Completed March 22, 1982  
 Application for plugging filed July 22, 1983  
 Plugging commenced August 18, 1983  
 Plugging completed August 31, 1983  
 Reason for abandonment of well or producing formation Uneconomical to operate

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Buddy Metz

Producing formation LKC Depth to top 3803 bottom 3992 T.D. PB 4040'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface	Water	0'	300	8 5/8	288	-0-
Production	Oil & Water	0'	4546	5 1/2	4546	3031.10'


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet for each plug set. MIRU Hembree WS DD Unit. Pulled rods; pump & tbg. WIH w/ret. head and 125 its 2 3/8" OD tbg. MIRU Sun Cmtg and load hole w/wtr to kill well. COOH w/tbg & perma-trieve. SI. Rel Sun & Hembree. On 8-20-83 MIRU Sun to 5 1/2" csg and pumped 75 sx 50-50 Pozmix cmt w/2% gel, 3% CaCl. Rel. wiper plug and displ to 3750 w/89 BSW. Final press 500#. SI. RDMO Sun. On 8-23-83 MIRU Kelso Csg. Pullers. Dug out cellar and pull stretch on pipe. SDON. Shoot pipe @3210'. Pipe would not come loose. Shoot pipe @ 3030'. Pull & LD 67 its 5 1/2" csg. RDMO Kelso. On 8-31-83 MIRU Sun Cmtg to 8 5/8" and plg as follows: Mixed 4 sx cotton seed hulls, 15 sx gel, 50 sx 50-50 Pozmix w/2% gel and 3% CaCl, 15 sx gel, 1 sk cottonseed hulls. Release 8 5/8" wiper plug, mix 130 sx 50-50 Pozmix w/3% aCl & 2% gel/sk. ISIP - 200#. RDMO Sun. State plugger on loc. To weld plate on 8 5/8" csg. Well P&A August 31, 1983

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pullers, Inc.  
Chase, Kansas

STATE OF Kansas COUNTY OF Barton, ss.  
J. R. Miller (employee of owner) or (owner or operator) of the

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) J. R. Miller Off. Mgr.  
Box 287, Great Bend, Kansas 67530  
 (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of September, 1983

My Commission expires: February 15, 1984

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 2 1983  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

15-151-20908-0000

SIDE TWO

WELL LOG

Show all important zones of porosity and contents thereof, cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS ETL, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface	0'	301'	Formation Tops:	
Shale	301'	550'	Heebner	3613'
Lime & Shale	550'	1885'	Brown Lime	3772'
Lime & Shale	1885'	2455'	LKC	3798'
Lime & Shale	2455'	3295'	Mississippi	4192'
LKC	3295'	3965'	Viola	4302'
Simpson	3965'	4373'	Simpson	4380'
Total Depth	4550'		Arbuckle	4482'

RECEIVED  
STATE CORPORATION COMMISSION

JUL 25 1963

CONSERVATION DIVISION  
Wichita, Kansas

7-25-63