

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Pratt County, Sec. 11 Twp. 26 Rge. 14 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NE NE  
Lease Owner California Time Petroleum Company  
Lease Name Bobby Moore #1 Well No.  
Office Address Beverly Hills, California  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 10/10/69 19  
Plugging completed 10/21/69 19  
Reason for abandonment of well or producing formation depleted



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Warren  
Producing formation Depth to top Bottom Total Depth of Well 4351 Feet  
Show depth and thickness of all water, oil and gas formations.

1-15-70

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	TO	SIZE	PUT IN	PULLED OUT
		8-5/8	262	none
		5 1/2"	4343'	2348'

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 15 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom, ran sand to 4200', dumped 3 sacks of cement.  
Shot pipe at 3811, 3715', worked pipe to 25" tension. Checked hole, found bridge at 2797', ran 2" bailer, fished wire line out, checked hole, top of mud was 2772', pumped mud out of pipe, shot pipe at 3205, 3110', 3015', 2923', 2824', 2733', 2638', 2548', 2453', 2361', worked pipe loose, pulled 76 joints. Halliburton pumped 15 sacks mud, 75 sacks of cement to plug well.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
NOEL J. KNIGHT

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
CHASE, KANSAS  
(Address)

Subscribed and sworn to before me this 14th day of January, 1970

My commission expires 2/15/71

[Signature]  
Notary Public.

**DRILLERS LOG**

W1 Hobby Moore

CASING RECORD:  
254.55' of used  
8-5/8" casing.

COMPANY: Time Petroleum Company

DESCRIPTION: SW SW NE  
Section 11-26-14W  
Pratt County, Kansas

TOTAL DEPTH:  
4351'

COMMENCED: May 6, 1965

ELEVATION: 1982' KB

COMPLETED: May 17, 1965

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	200	Ran 254.55' of used 8-5/8" surface casing; set and cemented at 262' with 300 sacks of cement, 2% gel and 3% calcium chloride. Cement circulated. Plug down at 9:15 A. M. May 7, 1965.  Ran 6 drill stem tests.  Ran Electra log.
Shale	200	470	
Sandy Shale & Red Bed	470	894	
Anhydrite	894	1860	
Shale & Shells	860	1821	
Lime	1821	1945	
Lime & Shale	1945	2415	
Lime	2415	2578	
Lime & Shale	2578	3044	
Shale & Lime	3044	3225	
Lime & Shale	3225	3810	
Lime	3810	4160	
Shale & Sand	4160	4210	
Lime	4210	4267	
Lime & Chert	4267	4334	
Cherty Lime	4334	4337	
Sand	4337	4351	

TOTAL DEPTH 4351'

Ran 141 joints of new 4 1/2" (4360.37') casing; set and cemented at 4343' with 75 sacks of poxmix, salt saturated. Plug down at 10:50 P. M. May 17, 1965.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 18 1969  
CONSERVATION DIVISION  
Wichita, Kansas

7-18-69

STATE OF KANSAS }  
COUNTY OF BARTON) ss.

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Jim B. McWilliams  
Jim B. McWilliams, Secy-Treas.

Subscribed and sworn to before me this 18th day of May, 1965.

Elaine B. Taylor  
Elaine B. Taylor, Notary Public

My Commission Expires:

December 14, 1965