


15-151-10937-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

PRATT County. Sec. 11 Twp. 26S Rge. 14W (E) (W)
Location as "NE/CNW%SW%" or footage from lines SW NW NE
Lease Owner K & E DRILLING, INC.
Lease Name WEBSTER Well No. 1
Office Address 719 Union Center, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-19-57 19
Application for plugging filed 5-19-57 19
Application for plugging approved 5-19-57 19
Plugging commenced 5-19-57 19
Plugging completed 5-19-57 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives, Box 8, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4414 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	370	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill hole with heavy mud to 350' set plug & set with 20 sx cement thru drill pipe. Fill with heavy mud to 35' of base of cellar. Set solid bridge with 10 sx cement. Plugging Complete.

5-24-57

FILED
STATE OF KANSAS
MAY 24 1957
WICHITA

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E DRILLING, INC.
Address 719 Union Center Building, Kansas (Wichita)

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Dale Silcott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott
Dale Silcott of K & E DRILLING, INC.
719 Union Center Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of May, 19 57

Patricia M. Edwards, Notary Public.

My commission expires 11 August 1958.

PLUGGING
FILE SEC. 11 T. 26 S. 14 W.
BOOK PAGE 14 LINE 2

W E L L L O G

OPERATOR: K & E DRILLING, INC.
 719 Union Center Building
 Wichita 2, Kansas

CONTRACTR: K & E DRILLING, INC.
 719 Union Center Building
 Wichita, Kansas

CASING: 8-5/8" @ 370' (300 sx)

R.T.D. 4414'

FARM NAME: #1 WEBSTER

LOCATION: SW NW NE,
 Sec. 11-26S-14W
 Pratt Co, Kansas

COMMENCE: 5-7-57
 COMPLETED: 5-19-57

PRODUCTION: D & A

ELEVATION: 1983' KB

FORMATION RECORD

Depths shown indicate the bottom of formations encountered.

Shale	30
Sand	80
Shale	140
Sand	210
Shale & Shells	372
Shale & Red Bed	795
Shale	870
Anhydrite	843
Shale & Shells	1855
Lime	2140
Lime & Shale	2365
Lime	2485
Lime & Shale	3430
Shale & Lime	3580
Lime	3700
Lime & Shale	3800
Lime	4215
Lime & Shale	4245
Shale	4270
Lime	4310
Cherty Lime	4365
Lime	4414
R.T.D.	4414

5-24-57

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 24 1957
 CONSERVATION DIVISION
 Wichita, Kansas

CERTIFICATION

STATE OF KANSAS)
 ") SS:
 COUNTY OF SEDGWICK)

I, Dale Silcott, of K & E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the log of the #1 WEBSTER well.

Dale Silcott
 Dale Silcott

Subscribed and Sworn to before me this 23rd day of May 1957

Patricia M. Edwards
 Patricia M. Edwards, Notary Public

My commission expires: 11 August 1958.

PLUGGING
 FILE SEC 11 T 26 14W
 BOOK PAGE 14 LINE 2