


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 13 Twp. 27S Rge. 6 (W)

Location as "NE/CNW%SW%" or footage from lines C NE SE
Lease Owner Mack Oil Company
Lease Name Phil Well No. 1
Office Address 812 Union Center Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-14 19 63
Application for plugging filed 12-15 19 63
Application for plugging approved 12-15 19 63
Plugging commenced 12-15 19 63
Plugging completed 12-15 19 63
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Archie Elving
Producing formation None Depth to top Bottom Total Depth of Well 4185' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set 35 sx @ 300'
10 sx @ 40'
5 sx @ Rat hole and Mouse hole

RECEIVED
STATE CORPORATION COMMISSION
12-18-63
DEC 18 1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mack Oil Company
Address Box 400, Duncan, Oklahoma

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Robert L. Harris (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert L. Harris
812 Union Center Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of December, 19 63

My commission expires 2-7-66

Donald L. Iron
Notary Public.

MACK OIL COMPANY
Duncan, Oklahoma

DRILLERS WELL LOG

Phil #1

Commenced R.D.: 11-29-63
Completed R. D.: 12-14-63
Total Depth: 4185'

C NE SE Sec. 13-27S-6W
Kingman County, Kansas
Elevation: 1494 K.B.
Initial Production: Dry Hole
Contractor: Mack Oil Company

<u>STRATA</u>	<u>DEPTH</u>
Surface Hole	0 - 70
Shale	70 - 298
Shale & Sand	298 - 895
Shale & Shells	895 - 1180
Anhydrite	1180 - 1200
Shale & Lime	1200 - 1250
Lime	1250 - 1825
Lime & Sand	1825 - 1875
Shale & Shells	1875 - 2078
Lime & Shale	2078 - 2446
Lime	2600 - 2689
Shale & Shells	2689 - 2865
Shale & Lime	2865 - 3048
Lime	3048 - 3743
Lime & Chert	3743 - 3847
Lime	3847 - 3871
Lime & Chert	3871 - 3916
Chert	3916 - 3939
Chert & Lime	3939 - 3968
Chert	3968 - 3989
Lime & Chert	3988 - 4005
Chert	4005 - 4018
Lime & Shale	4018 - 4057
Shale & Chat	4057 - 4123
Lime	4123 - 4185

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

MACK OIL COMPANY

By: Robert L. Harris

Signed and sworn to in my presence this 16th day of December, 1963,
by Robert L. Harris, representative of Mack Oil Company.

Ronald L. Irion
Ronald L. Irion
Notary Public

My commission expires: 2-7-66