

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Reno County. Sec. 9 Twp. 23 Rge. 7 (E) W(W)

Location as "NE/CNW/SW" or footage from lines SE SE SE

Lease Owner Anschutz Drilling Company, Inc.

Lease Name Wiegel Well No. 1

Office Address 709 Union National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 31 19 56

Application for plugging filed August 31 19 56

Application for plugging approved August 31 19 56


Plugging commenced August 31 19 56

Plugging completed August 31 19 56

Reason for abandonment of well or producing formation oil in commercial quantities not found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4075 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	193'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 190'. Set #1 plug with 15 sacks cement. Filled hole with extra heavy rotary mud from plug #1 to top. Set #2 plug at top with 5 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Drilling Company  
Address 814-16 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF Sedgwick, ss.  
R. R. McNicol (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. R. McNicol  
814-16 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of September, 19 56

Darlene May  
Notary Public.

My commission expires September 30, 1959

PLUGGING  
FILE SEC. 9 T. 23 R. 7 W  
BOOK PAGE 95 LINE 45

RECEIVED  
STATE CORPORATION COMMISSION  
09-09-56  
CONSERVATION DIVISION  
Wichita, Kansas

15-155-00028-0000

ROTARY DRILLING LOG

OPERATOR: AnschutzDrilling Company, Inc.  
Wiegel #1  
SE SE SE Sec. 9-23-7W,  
Reno County, Kansas

CONTRACTOR: Prime Drilling Company  
COMM: 8/15/56  
COMP: 8/31/56

Formations:

Remarks: Set 8-5/8" surface casing at  
193' cemented with 175 sacks Pozmix, 2%  
C.C.

Sand & Gravel	189'
Shale	210'
Red Bed & Shale	695'
Anhydrite	710'
Shale & Shells	980'
Salt Lime & Shale	1210'
Lime Shale & Sand	1425'
Shale & Lime	2760'
Lime	2785'
Lime & Sandy Lime	2940'
Lime & Shale	3025'
Lime	3519'
Lime & Shale	3560'
Shale	3591'
Mississippi	3597'
Miss. Chat	3607'
Mississippi	3685'
Lime & Shale	3725'
Shale	3850'
Shale & Lime	3925'
Sand & Shale	4050'
Arbuckle	4075'
Rotary Total Depth (D&A)	4075'

We certify the above log is true and  
correct to the best of our knowledge  
and belief.

PRIME DRILLING COMPANY

*R.R. Mc Nicol*

R. R. Mc Nicol

PLUGGING			
FILE	SEC. 9	T. 23	R. 7W
BOOK	PAGE 95	LINE	45

RECEIVED  
COMMISSION  
SEP 6 1956  
CONSERVATION DIVISION  
Wichita, Kansas