

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-155-20,629-0000

LEASE NAME Krehbiel

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section Line
 C NE SW 4

 Ft. from E Section Line

LEASE OPERATOR Commonwealth Petroleum Corp.

SEC. 19 TWP. 23 RGE. 7 (E) or (W)

ADDRESS P.O. Box 2458, Hutchinson, Ks. 67504

COUNTY Reno

PHONE# (316) 463-5461 OPERATORS LICENSE NO. 3243

Date Well Completed 12-18-79

Character of Well D&A

Plugging Commenced 2-10-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-13-89

The plugging proposal was approved on 2-10-89 (date)

by Don Thompson (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? N/A

Producing Formation 3765 Depth to Top Bottom T.D. 3789

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	250	8 5/8		0
		0	3788	4 1/2		2,980

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Fill with sand to 3715 & dump 4 sxs. cement.

Spot 25 sxs. cement @ 1150 ft., & 25 sxs. @ 700 ft. & 35 sxs. @ 300 ft. -
then space with gel to 60 ft., then cir. cement to surface from 60 ft.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Nicholas Casing Pulling License No. 6698

Address P.O. Box 108, Geneseo, Ks. 67444

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Commonwealth Petro., Corp.

STATE OF Kansas COUNTY OF Rice, ss.

(Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) Allen A. Schiefel

(Address) Box 108 - Geneseo, Ks 67444

SUBSCRIBED AND SWORN TO before me this 16th day of February, 19 89



Marsha S. Huggans
Notary Public

Commission Expires: Sept. 1, 1990