

130 S. Market, Room 2078  
Wichita, Kansas 67202

**Well Plugging Record**  
**K.A.R. -82-3-117**

API NUMBER 15-155-21448-0000  
LEASE NAME Miller  
WELL NUMBER 2-20

TYPE OR PRINT

NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

4950 Ft. from South Line of Section  
2970 Ft. from East Line of Section

LEASE OPERATOR Phillips Exploration Company, LC SPOT LOCATION NE NE NW  
ADDRESS 4109 N. Ironwood Section 20 Township 23s Range 7w  
CITY, STATE, ZIP Wichita, Kansas 67226 County Reno  
PHONE # 316-636-2256 Date Well Completed October 9, 2000  
Character of Well Dry and Abandoned Date Plugging Commenced October 9, 2000  
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed October 9, 2000

The plugging proposal was approved on October 5, 2000 (date)  
by Virgil Clothier (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes  
Producing Formation(s) D&A Depth to Top Bottom T.D. 3800

Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS**

**CASING RECORD**

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	38	and		
Redbeds	Shale	38	250	8-5/8"	237.11'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet each set.

10/9/00 using 150sx 60/40 Poz 4% Gel as follows: Heavy mud from 3800' to 1150', then 35sx, heavy mud to 650', then 35sx, heavy mud to 300' then 35sx, heavy mud to 60' then 20sx to surface.  
Plugged rathole with 15 sacks and mousehole with 10 sacks. Plug down at 9:30 am on 10/9/00  
by Allied. Ticket # 4297.

Name of Plugging Contractor Sterling Drilling Company  
Licence No. 5142  
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124  
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Phillips Exploration Company, LC (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) *Gary M. Talbott*  
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 9th day of October, 2000



My Commission Expires: \_\_\_\_\_

*Pamela S. Fields*  
(Notary Public) STATE CORPORATION COMMISSION

RECEIVED

OCT 10 2000

CONSERVATION DIVISION  
Wichita, Kansas

Form CP-4  
Revised 12-92

*(Handwritten initials)*