

15-155-00291-0000


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Reno County, Sec. 30 Twp. 23 Rge. 7 (E) W (W)

Location as "NE/CNW/SW" or footage from lines N/2 N/2 NW/4
Lease Owner J. W. Braden Oil Company
Lease Name Russell Well No. 2
Office Address Hutchinson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed January 13, 1955 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 2-7 19
Plugging completed 2-11 19
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee, McPherson, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole with chat from 3456' to 3430'
Dumped 6 sacks cement from 3430' to 3390'
Filled with mud to 200' and placed rock bridge
Dumped 30 sacks cement from 200' to 140'
Filled with mud to 20' and placed rock bridge
Capped with 5 sacks cement to cellar base
Surface casing left in hole

STATE CORPORATION COMMISSION
FEB 26 1955
02-26-55
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Morgan Well Plugging Service
Address Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.
J. W. Braden (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. W. Braden
P.O. Box 266, Hutchinson, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of February, 19 55
M. L. Bowman

My commission expires March 4, 1957 Notary Public.

PLUGGING
FEB SEC 30 T 23 R 7W
PAGE 96 LINE 25

Russell #2

Operator: J. W. Braden Oil Company

N/2 N/2 NW/4

30-23S-7W

Contractor: Braden Drilling Company

René County, Kansas

Test Commenced: 12-27-54

Test Completed: 1-13-55

Casing Record: Set 150' of 8-5/8" casing with 125 sacks cement,
2% c.c. Set 1076' of 5 1/2" with 150 sacks cement.

Clay & sand	40
Red rock, shale & shells	490
Shale & shells	620
Salt & shells	820
Shale & shells	1115
Anhydrite	1145
Shale & lime	1420
Lime	1820
Shale & shells	2215
Lime	2300
Lime & shale	2625
Lime	2885
Lime & shale	3140
Lime	3840
Shale & lime	3977
Lime	4045
Shale	4073
Shale & lime	4078 T. D. R. B.

STATE OF KANSAS,)

(SS: -

SEBICK COUNTY,)

I hereby certify that the above information is true and correct as revealed by the records of the Braden Drilling Company.

Norman Patrick

Subscribed and sworn to before me this 14th day of January, 1955.

Norma Riskey
Notary Public

My commission expires April 29, 1957.

PLUGGING
FILE REC 30-23R-7W
BOOK PAGE 96 LINE 25

RECEIVED
STATE OF KANSAS
FEB 26 1955
CONSERVATION DIVISION
Wichita, Kansas