


15-155-20326-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
245 North Water
Wichita, KS 67202

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Reno County, Sec. 30 Twp. 23 Rge. 7 (E) (W)
Location as "NE/CNW/SE/SW" or footage from lines. 150' FNL of N/2 of NW
Lease Owner Search Drilling Company
Lease Name McArthur #1 Well No.
Office Address Wichita, Kansas 67218
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19__
Application for plugging filed 19__
Application for plugging approved 19__
Plugging commenced 3/22/76 19__
Plugging completed 3/24/76 19__
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation Depth to top Bottom Total Depth of Well 3661
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	160	none
				5 1/2"	3641	3393'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded back to 3400' and ran 5 sacks cement.
Loaded hole, shot pipe at 3358', pulled 109 joints of 5 1/2" casing. Pumped 3 sacks hulls, 20 sacks gel and 85 sacks cement, 50-50 pos.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

MAR 26 1976
03-26-76

RECEIVED BY MAIL
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS (Address)

Subscribed and sworn to before me this 25th day of March 1976

My commission expires
NOTARY PUBLIC
MARGARET MELCHER
Rice County, Ks.
My Comm. Exp. Feb. 15, 1979

Margaret Melcher
Notary Public.

DRILLERS LOG

15-155-20326-0000

McArthur #1

CASING RECORD:

8 5/8" set at 160'
with 150 sacks cement

TOTAL DEPTH:
3661'

OPERATOR: Mid-Continent Energy Corp.

CONTRACTOR: Search Drilling Company

COMMENCED: January 21, 1976

COMPLETED: January 28, 1976

DESCRIPTION:

NW NE NW,
Section 30-23S-7W
Reno County,
Kansas

FORMATION

FROM

TO

REMARKS

Sand and Clay	0	30	
Red Bed and Shale	30	160	
Shale	160	1040	
Anhydrite	1040	1060	
Shale and Lime	1060	1750	
Lime and Shale	1750	3466	
K. C. Lime	3466	3481	
Lime and Shale	3481	3655	
Miss. Shale	3655	3661	
RTD	3661		

RECEIVED
SEARCH DRILLING COMPANY

MAR 15 1976

SEARCH DRILLING COMPANY
Wanda, Kansas

Ran 120 joints of
5 1/2" - 1' off
bottom - cemented
with 50 sacks
posmix, 18% salt
saturated, 3/4 of 1%
CFR2, preceded by
20 barrels salt flush
plug down at 10:30 P.M.

I certify that this is a true and correct copy of the above log to the best of knowledge.

SEARCH DRILLING COMPANY

R. M. Wendling
R. M. Wendling

Subscribed and sworn to before me this 30th day of January, 1976

My commission expires:

Feb. 1977
MAXINE DRESSSEN
NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. FEB. 19, 1977

Maxine Dresssen
Maxine Dresssen

Notary Public