

Form GP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 18 1965
1-18-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Mack Oil Company

Complete Address: 812 Union Center Bldg., Wichita, Kansas

Lease Name Glenna Well No. # 1

Location C NE NW Sec. 17 Twp. 27 Rge. 6 (E) (W) W

County Kingman Total Depth 4130

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Mack Oil Company

Address: 812 Union Center Bldg., Wichita, Kansas License No.

Operation Completed: Hour 11:00AM Day 17th Month Jan. Year 1965

The Above well was plugged as follows:

286' of 8 5/8" surface pipe, cement circulated with 235 sacks. Hole
was filled with drilling mud to 250', 1st cementing plug, bridged
solid with hulls on fluid at 250', and cemented with 25 sacks on plug
at 240'. Hole was filled with drilling mud to 40', 2nd cementing plug,
bridged solid with hulls on fluid at 40', and cemented with 10 sacks
to the base of the cellar.
Rat and mouse hole bridged and cemented with 5 sacks.

I hereby certify that the ~~above well~~ **INVOLVED** was plugged as herein stated.

DATE 1/18/65
INV. NO. 545-W

Signed: Archie Elving
Well Plugging Supervisor