

15-095-30121-0000

Form GP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
12-9-66
DEC 9 1966
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Shawver Armour, Inc.
Complete Address: 817 Central Bldg., Wichita, Kansas
Lease Name Hampel Well No. # 1
Location SE SE Sec. 7 Twp. 27 Rge. 6 (E) (W) W
County Kingman Total Depth 3460'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated: _____
Plugging Contractor: Shawver Armour, Inc.
Address: 817 Central Bldg., Wichita, Kansas License No. _____
Operation Completed: Hour 12:00PM Day 7th Month Dec. Year 1966

The Above well was plugged as follows:

245' of 8 5/8" surface pipe, cement circulated with 230 sacks. Hole
was filled with drilling mud to 240', 1st cementing plug, bridged with
1 sack of dry cement and 1/2 sack of hulls on fluid at 240', and cemented
with 24 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at
40', and cemented with 9 sacks to the base of the cellar. Rat hole
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12/9/66
INV. NO. 4439-11