

15-155-20324-0000

API NUMBER 15-155- 20,324

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE NW NW, Sec. 10, T 23 S, R 7 W

R

\_\_\_\_\_ feet from N/S section line  
\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5944

Lease Name Weigle B Well # 1

Operator: Cress Oilfield Serv. Inc.  
Name & Address Burns, Ks.

County Reno

Well Total Depth 3640 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 7/8 feet 250"

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor BJS Well Service License Number \_\_\_\_\_

Address Winfield Ks. 67156 608 W. 8th St.

Company to plug at: Hour: 3:00 AM, Day: 8 Month: Oct Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO \_\_\_\_\_

(company name) \_\_\_\_\_ (phone) 316-221-2030

were: Plug Bottom with 4 sacks Cement @ 3550'  
Top. Pump 100 sacks thru 8 7/8 swage fill to  
top

Signed Glen L. Ward  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None \_\_\_\_\_

Operations Completed: Hour: 3:00 P.M., Day: 8 Month: Oct Year: 1982

ACTUAL PLUGGING REPORT Pipe set @ 3640. Plug set @ 3630. Perf. 3587-91 @  
3555-56'. Top of Perf. 3555. Sand to 3550 then  
Dumped 4 sack of Reg. Cement. Shot pipe @ 2517  
& Recovered 2517' of 4 1/2" casing. Mixed 4 sacks  
of Gel. & 4 sacks Halls & 100 sacks of Reg. Cement Pumped  
down 8 7/8 Pipe max. psi 750' closed in @ 250 PSI filled to

Remarks: top. Halliburton ticket 233254

RECEIVED  
STATE CORPORATION COMMISSION

OCT 18 1982  
10-18-82

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED

DATE 11-15-82  
INV. NO. 1552-W

Signed Glen L. Ward  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82

**HALLIBURTON**  
Services

**BULK MATERIALS DELIVERY  
AND  
TICKET CONTINUATION**

15-155-20324-0000

FOR INVOICE AND  
TICKET NO.

A Division of Halliburton Company  
DUNCAN, OKLAHOMA 73536

DATE <b>10/8/82</b>	CUSTOMER ORDER NO.	WELL NO. AND FARM <b>Weigle B-1</b>	COUNTY <b>Remo</b>	STATE <b>Ks.</b>
CHARGE TO <b>Kanggs Boursche.</b>		OWNER <b>Same</b>	CONTRACTOR <b>C and S Well Service</b>	
MAILING ADDRESS		DELIVERED FROM <b>Great Bend, Ks.</b>	LOCATION CODE <b>50320</b>	PREPARED BY <b>T. Smith</b>
CITY & STATE		DELIVERED TO <b>Location</b>	TRUCK NO. <b>9066-6604</b>	RECEIVED BY
<b>No. B 233254</b>				

PRICE REFERENCE	SECONDARY REF. OR PART NO.	CODE		DESCRIPTION	UNITS 1		UNITS 2		UNIT PRICE	AMOUNT		
		L	D		QTY.	MEAS.	QTY.	MEAS.				
504-043		1	b	Regular Portland	100	sk			5.25	525	00	
509-406		1	b	2% Calcium Chloride Blended W/100	2	sk			21.00	42	00	
509-554		1	b	Halliburton Gel Sack	4	sk			6.30	25	20	
THIS IS NOT AN INVOICE												
		Returned Mileage Charge	TOTAL WEIGHT		LOADED MILES		TON MILES					
		SERVICE CHARGE ON MATERIALS RETURNED							CU. FEET			
500-207		1	b	SERVICE CHARGE			CU. FEET	104	.95	98	80	
500-306		1	b	Mileage Charge	9,960	66	328.68		.70	230	08	
				TOTAL WEIGHT	LOADED MILES		TON MILES					
No. <b>B 233254</b>		CARRY FORWARD TO INVOICE							SUB-TOTAL		921 08	

RECEIVED  
STATE CONSERVATION COMMISSION  
OCT 18 1982  
CONSERVATION DIVISION  
Wichita, Kansas