

15-207-19333-000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO: 44-39

LOCATION E/2 NE/4

SEC. 20 TWP. 23 RGE. 14E

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Peck

Operator R.E.French Address Gridley, Kansas

Field _____ County ~~#####~~ Coffey *Woods*

Total Depth 1666' Feet.

(Describe briefly the manner in which the well was plugged)

Bottom hole mudded heavy with heavy mud,
Hole bridged at 150' with wood ,rock and
cemented with 7 sacks, mud to 10', this
was all completed Sept; 29th, Mr French
finished plugging Oct; 11,1952 , 3sackg
was put on the 10' bridge and covered with soil.

PLUGGING
FILE REC 20 T 23 R 14 E
BOOK PAGE 47 LINE 39

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1952
CONSERVATION DIVISION
Wichita, Kansas Date Oct; 13th 1952
J.W. Hartbrook
District Conservation Agent

F

Well Record

Well No. 2 Owner - H.E. French Gridley, Kans.
 Located - 390 ft. west of east line, 2380 ft. south of north line
 East half of N.E. Q1 Sec. 20-23-14

On location July 11, 1952 Cemented 5 1/2" casing July 29, 1952

Casing -----
 8" set 980 ft. - Pulled
 7" " 1335 ft. - "
 5 1/2" set 1643 ft. Cemented with 20 sax.

Figures indicate bottom of formation

Soil & Clay	10 ft.	Lime	1270
Lime & shells	20	Shale	1300
Shale	30	Lime	1305
Lime	100	Shale	1628
Shale	170	Top of Wise Lime	1638 ft.
Lime	190	Wise Lime	1651
Shale	300	Slight show oil	1651
Lime	305	Brown Lime-soft.	
Shale	325	little Oil	1656 ft.
Lime	345	Brown - some lighter	
Shale	490	very soft-little oil	1659 ft.
Lime	550	Hard lime - white	1666 ft.
Shale	555	Total depth	1666 ft.
Lime	690		
Shale	715		
Lime	770	Aug.	
Shale	780		
Red Rock	785		
Lime	790		
Shale	810		
Lime	860		
Sand	865		
Lime	950		
Shale	1090		
set 3" pipe - 980 ft.			
Lime	1110		
Shale	1140		
Shale	1160		
Lime	1165		
Shale	1180		
Lime	1195		
Shale	1200		

RECEIVED
 STATE CORPORATION COMMISSION

OCT 15 1952

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 20 23 14
 BOOK PAGE 44 LINE 22