

To: 1 031393
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 151-21,885-00-00

E/2 SE NE, SEC. 25, T 26 S, R 13 W/4

TECHNICIAN'S PLUGGING REPORT

4-15

Operator License # 3911

3300 feet from S section line

330 feet from E section line

Operator: RAMA Operating Co., Inc.

Lease Name Hoeme Well # 1

Name & Address P.O. Box 159

County Pratt

Stafford, KS 67578

Well Total Depth 4319 140.36 feet

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 332

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 15 Month: 4 Year: 19 96

Plugging proposal received from Darrel Kelso

(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

were: 5 1/2" at 4316' w/75 sx cement, Perfs at 3764-70, 3862-66'

1st plug sand back to 3700' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 15 sx gel, 60 sx cement, 15 sx gel, 1 sx hulls, and 155 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:45 p.m. Day: 15 Month: 4 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3700' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 15 sx gel, 60 sx cement, 15 sx gel, 1 sx hulls, and 155 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

KANSAS CORPORATION COMMISSION

4-18-96
APR 18 1996

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2762' of 5 1/2" casing. WICHITA, KS

(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby certify that I have observed this plugging.

DATE APR 22 1996

Signed Steve Durrant (TECHNICIAN)

INV. NO. 49381