

9-12 15-151-10768-00-02

To: 1 040470
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #D-6005

C NW, SEC. 25, T 26 S, R 13 W/8

3960 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9232

Lease Name Lunt Well # 6

Operator: Timberline Oil & Gas Corporation
Name & Address 4447 S. Canyon Rd., Suite 1
Rapid City, SD 57702

County Pratt 148.36

Well Total Depth 4565 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 380

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Timberline Oil & Gas Corp. License Number 9232

Address 4447 S. Canyon Rd., Suite 1, Rapid City, SD 57702

Company to plug at: Hour: 9:30 a.m. Day: 12 Month: 9 Year: 19 90

Plugging proposal received from Terry McCune

(company name) Timberline Oil & Gas Corp. (phone) 316-672-9476

were: 7" at 4390' w/150 sx cement, Open hole at 4390-4565'

Hole in casing between 766-805' G.L. Casing collapsed at 1240' G.L. Top of parted tubing at 1240' G.L.

1st plug pump 50 lbs. hulls and 164 sx cement down 7" casing,

2nd plug pump 75 sx cement down 7" casing,

3rd plug pump 120 sx cement down 7" casing.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 12 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT Broke circulation out 7"/10 3/4" annulus, circulated hole with

80 barrels of fresh water, pumped down 7" casing with 164 sx 65/35 Pozmix 8% gel. Mixed

50 lbs. hulls in with cement. Followed down 7" casing with 75 sx 60/40 Pozmix,

Followed with 120 sx of 65/35 Pozmix 8% gel. Lost circulation. Rate 3 PBM @ 300#.

Shut in well at 300#. 9/12/90 @ 10 a.m. -Cement top on 7"/10 3/4" annulus found

350'. Annulus was 1" to surface from 350' w/90 sx cement-65/35 Pozmix 8% gel. 7" casing was topped out with 10 sx 65/35 Pozmix 8% gel.

Remarks: Cemented by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED (copy to observe this plugging.)

DATE 10-10-90

INV. NO. 29620

Signed Steve Pfeifer (TECHNICIAN)