

State of Kansas



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1965

CONSERVATION DIVISION
WICHITA, KANSAS

12-23-65

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Jack Dunham of Aspen Drilling Company has this
date requested permission to plug the following described well:

Mr. Dunham guarantees payment of the plugging fee.

Operator's full Name: Leben Drilling, Inc.

Complete Address: 815 Wichita Plaza, Wichita, Kansas

Lease Name: Hoener Well No. # 1

Location: C N/2 NE SW Sec. 27 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 3187' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dunham was instructed to plug the well as follows:

302' of 8 5/8" surface pipe, cement circulated with 225 sacks.

Fill hole with drilling mud to 260', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling mud

to 40', 2nd cementing plug, bridge with hulls, and cement with 10

sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Achie Elving
Conservation Division Agent