

State of Kansas



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg.
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

MAY 25 1965
5-25-65

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Claude Norwood of Leben Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Martin & Keller

Complete Address: 1035 Kennedy Bldg., Tulsa 3, Oklahoma

Lease Name: Repp Well No. # 1

Location: C NW NW Sec. 27 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4447' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

305' of 8 5/8" surface pipe, cement circulated with 200 sacks.
Fill hole with drilling mud to 275', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent