

State of Kansas



JOHN ANDERSON, Jr. Governor  
WILLIAM L MITCHELL Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Council

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 9 1965  
3-9-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Howard Roberts of Strata Drilling Inc. has this date requested permission to plug the following described well:

Mr. Roberts guarantees payment of the plugging fee.

Operator's full Name: Time Petroleum Company

Complete Address: 815 Union National Bldg., Wichita, Ks.

Lease Name: Henderson "C" Well No. # 1

Location: C SW SE Sec. 2 Twp. 26 Rge. 14 (E) (W) W

County Pratt Total Depth 4360' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Roberts was instructed to plug the well as follows:

265' of 8 5/8" surface pipe, cement circulated with 300 sacks.

Fill hole with drilling mud to 240', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling

mud to 40', 2nd cementing plug, bridge with hulls, and cement

with 10 sacks to base cellar. Bridge and cement rat hole with

2 sacks. Bridge and cement mouse hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent