

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

JUL 19 1966

7-19-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Beardmore Drilling Company

Complete Address: 700 One-Twenty Bldg., Wichita, Kansas

Lease Name Lunt Well No. # 4

Location SW NW NW Sec. 25 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4355'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 3:30PM Day 16th Month July Year 1966

The Above well was plugged as follows:

379' of 8 5/8" surface pipe, cement circulated. 4347' of 5 1/2" long string,
cemented with 175 sacks. Plug back T.D. 4240'. Top perforation 4214'.
Bottom of the hole was sanded to 4200', and cemented with 5 sacks, through
the dump bailer. 3176' of 5 1/2" long string was recovered from the hole.
Bridge plug was pushed in fluid to 340', rock bridge from 340' to 330'.
5 sacks of cement was mixed in a barrel, and put on plug at 330', through
the dump bailer, and let set for days. Hole was bailed dry, and 20 sacks
of cement was added to the plug. Hole was filled with mud to 40', rock
bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 7/19/66
INV. NO. 3594-w