

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 5 - 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Dunne-Gardner Pet. Inc

Complete Address Suite 250 200 W Douglas Wichita, KS

Lease Name Soeken Well No. 1

Location SE/SW/SE Sec. 27 Twp. 26S Rge. 13 (E) (W)

County Pratt Total Depth 4425

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling Co Inc

Address Box 1082 Great Bend, KS License No. 623

Operation Completed: Hour 3:00 PM Day 3 Month 4 Year 1974

The above well was plugged as follows:

825 ft 8 5/8 surface cemented with 600 sacks. 4425 ft 4 1/2 long string
cemented with 200 sacks. Top perf. 3924 ft. Sand to 3900 ft, 4
sacks cement with bailer. Pulled 2700 ft 4 1/2. Pump 3 sacks hulle,
15 sacks gel, 125 sacks cement to surface.

Pumped by Allied Cementing Co Great Bend, KS

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 4/5/74
INV. NO. 8889-W