

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

3-5-65

MAR 5 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name R. W. Rine Drilling Company

Complete Address: 420 Union Center, Wichita, Kansas

Lease Name Hoener Well No. # 1-A

Location SW SW SW Sec. 27 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4484'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 2:30PM Day 4th Month March Year 1965

The Above well was plugged as follows:

835' of 8 5/8" surface pipe, cemented with 400 sacks. 4484' of 5 1/2" long
string, cemented with 240 sacks. Plug back to 3968'. Top perforation
3804'. Bottom of the hole was sanded to 3800', and cemented with 5 sacks.
3190' of 5 1/2" long string was recovered from the hole. Fluid in the hole
was bailed down to 300'. Bridge plug was set on fluid at 300', and 10'
of rock bridge, and cemented with 25 sacks. Hole was filled with mud to
40', and 10' of rock bridge, and cemented with 10 sacks to the base of
the cellar.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 3/5/65
INV. NO. 971-W

Signed: Archie Elving
Well Plugging Supervisor