

**KANSAS**  
**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
STATE CORPORATION COMMISSION

DEC 23 1965  
12-23-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Leben Drilling, Inc. & Explorer Oil Company

Complete Address: 815 Wichita Plaza, Wichita, Kansas

Lease Name Hoener Well No. # 1

Location C N/2 NE SW Sec. 27 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 3187'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Aspen Drilling Company

Address: Great Bend, Kansas License No.

Operation Completed: Hour 8:00AM Day 22nd Month Dec. Year 1965

The Above well was plugged as follows:

302' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fluid  
level in the hole was at 110'. 1st cementing plug and 1 sack of hulls  
was pushed in fluid to 260', and cemented with 25 sacks, through the  
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing  
plug, bridged solid with dry cement and hulls on fluid at 40', and  
cemented with 10 sacks to the base of the cellar. Rat hole bridged and  
cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Archie Elving  
Well Plugging Supervisor

DATE 12/27/65

INV. NO. 2467-11