

He
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 25 1965 5-25-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Martin & Keller

Complete Address: 1035 Kennedy Bldg., Tulsa 3, Oklahoma

Lease Name Repp Well No. # 1

Location C NW NW Sec. 27 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4447'

Abandoned Oil Well Gas Well Input Well BWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Inc.

Address: 815 Wichita Plaza, Wichita, Kansas License No.

Operation Completed: Hour 4:00 PM Day 24th Month May Year 1965

The Above well was plugged as follows:

305' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fluid
level in the hole was at 95'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 275', and cemented with 25 sacks, through the
drill pipe. Fluid level was now at 40', 1st cementing plug, bridged
solid with dry cement and hulls on fluid at 40', and cemented with
10 sacks to the base of the cellar. Rat hole bridged and cemented with
2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 5/26/65

INV. NO. 1211-W