

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
1-17-75
JAN 17 1975

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Allen Oil Co

Complete Address Box 339 Great Bend, KS

Lease Name H. Tregalias Well No. 4

Location NE/SE/NE Sec. 32 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4340

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co Inc

Address Box 364 Great Bend, KS License No. 399

Operation Completed: Hour 4:00 PM Day 16 Month 1 Year 1975

The above well was plugged as follows:

855 ft 10 3/4 surface cemented with 370 sacks. 4238 ft 5 1/2 long string
cemented with 200 sacks. Open hole. Sand to 4200 ft, 5 sacks cement
with bailer. Pulled 3117 ft 5 1/2. Set 10 ft rock bridge at 365 ft.
Fill hole with 7 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 1/17/75
INV. NO. 663-W