


15151-10804-00-00



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

1-10-75
RECEIVED
STATE CORPORATION COMMISSION
JAN 10 1975
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Allen Oil Co
Complete Address Box 339 Great Bend, KS
Lease Name Tregallas Well No. 2
Location SE/SW/NE Sec. 32 Twp. 26 Rge. 13 (E) (W) W
County Pratt Total Depth 4296
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Southwest Casing Pulling Inc
Address Box 364 Great Bend, KS License No. 399
Operation Completed: Hour 4:00 PM Day 7 Month 1 Year 1975

The above well was plugged as follows:
849 ft 10 3/4 surface cemented with 700 sacks. 4267 ft 5 1/2 long
string cemented with 150 sacks. Open hole. Sand to 4250 ft, 5 sacks
cement with bailer. Pulled 1944 ft 5 1/2. Set 10 ft rock bridge at
255 ft. Fill hole with 5 1/2 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 1/10/75
INV. NO. 628-W