

15-151-10803-00-60



Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JAN 28 1975

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Allen Oil Co

Complete Address Box 339 Great Bend, KS

Lease Name Tregallas Well No. 1

Location NE/NE/NE Sec. 32 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4286

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Southwest Casing Pulling Inc

Address Box 364 Great Bend, KS License No. 399

Operation Completed: Hour 11:00 AM Day 25 Month 1 Year 1975

The above well was plugged as follows:  
859 ft 8 5/8 surface cemented with 500 sacks. 143 ft 13 3/8 surface  
cemented with 200 sacks. 4260 ft 5 1/2 long string cemented with 150 sks.  
Open hole. Sand to 4250 ft, 5 sacks cement with bailer. Pulled  
3360 ft 5 1/2. Set 10 ft rock bridge at 265 ft. Fill hole with 3 1/2 yds  
redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 1/30/75  
INV. NO. 715-W