

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
AUG 2 1966
3-66

Operator's Full Name Pipe Pullers, Inc.

Complete Address: Box 486, Ellinwood, Kansas

Lease Name Calbeck Well No. # 12

Location NW SW NE Sec. 33 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4473'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Pipe Pullers, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 12:45 PM Day 29th Month July Year 1966

The Above well was plugged as follows:

872' of 8 5/8" surface pipe, cemented with 350 sacks. 4472' of 5 1/2" long
string, cemented with 250 sacks. Plug back T.D. 4437'. Top perforation 4290'.
Bottom of the hole was sanded to 4275', and cemented with 5 sacks, through
the dump bailer. Bridge plug was pushed in fluid to 325', rock bridge from
325' to 315'. 4 sacks of cement was mixed in a barrel, and put on plug at
315', through the dump bailer, and let set over-night. Next day hole was
bailed dry and 21 sacks of cement was added to the plug. Hole was filled
with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks
to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 8/3/66

INV. NO. 3288-11