

KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, KansasWell Plugging Authority,  
issued November 20, 1967.RECEIVED  
STATE CORPORATION COMMISSION  
FEB 8 - 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Spector Pipe & Supply, Inc.

Complete Address: Box 169, Russell, Kansas 67665

Lease Name Taylor Well No. # 1

Location SE NE NW Sec. 33 Twp. 26 Rge. 13 (E) W

County Pratt Total Depth 4420'

Abandoned Oil Well X Gas Well     Input Well     SWD Well     D & A    

Other well as hereafter indicated:    

Plugging Contractor: Lynch Casing Pulling Company

Address: R. R. # 4, Great Bend, Kansas 67530 License No. 457

Operation Completed: Hour 1:30PM Day 6th Month February Year 1968

The Above well was plugged as follows:

810' of 8 5/8" surface pipe, cemented with 775 sacks. 4420' of 5 1/2" long string,  
cemented with 150 sacks. Plug back T.D. 3800'. No record of perforations. Bottom  
of hole was sanded to 3750', and pressured up, pressure held. 5 sacks of cement  
was dumped at 3750', with cement from 3750' to 3710'. 3325' of 5 1/2" long string  
was recovered from the hole. Bridge plug was pushed in fluid to 400', bridge plug  
and rock bridge from 400' to 385'. 2 sacks of cement was mixed in a barrel, and  
put on plug at 385', through the dump bailer, and let set over-night. Next day  
hole was bailed dry, and 25 sacks of cement was added to the plug, with cement  
from 385' to 305'. Hole was filled with mud to 40', rock bridge from 40' to 30',  
and cemented with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Audie Elving  
Well Plugging Supervisor

INVOICED

DATE 2/8/68INV. NO. 7231-W