

10  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 22 1966  
8-22-66  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Pipe Pullers, Inc.

Complete Address: Box 486, Ellinwood, Kansas

Lease Name Galbeck Well No. # 2

Location SW NW NE Sec. 33 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4417 1/2"

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Pipe Puller, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 1:45PM Day 16th Month August Year 1966

The Above well was plugged as follows:

811' of 8 5/8" surface pipe, cement circulated. 4411 1/2' of 5 1/2" long string,  
cemented with 180 sacks. This is an open hole. Bottom of the hole was sanded  
4300', and cemented with 5 sacks. 2086' of 5 1/2" long string was recovered from  
the hole. Bridge plug was pushed in fluid to 325', rock bridge from 325' to  
315'. 5 sacks of cement was mixed in a barrel, and put on plug at 315', through  
the dump bailer, and let set over-night. Next day hole was bailed dry, and 20  
sacks of cement was added to the plug, Hole was filled with mud to 40', rock  
bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/22/66

INV. NO. 3791-4

Signed: Archie Elving  
Well Plugging Supervisor