

15-151-14840-50.00

Form CP-3  
Rev. 6-4-68

R

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED

SEP 19 1973

CONSERVATION DIVISION  
Wichita, Kansas  
9-19-73

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Dundee Pipe & Supply

Complete Address Box 2391 Tulsa, OK

Lease Name Strait Well No. 4

Location SW/SW/NW Sec. 33 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4434

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Russ Casing Pulling Co Inc

Address Box 1482 Great Bend, KS License No. 623

Operation Completed: Hour 1:00 PM Day 18 Month 9 Year 1973

The above well was plugged as follows:

775 ft 10 3/4 surface cemented with 500 sacks. 4431 ft 7" long string  
cemented with 200 sacks. Top perf. 4254 ft, sand to 4000 ft, 7 sacks  
cement with bailer. Pulled 2920 ft 7". Set 10 ft rock bridge at  
250 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 9-19-73

INV. NO. 7930-102