

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 8 1966

7-8-66

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pipe Pullers, Inc.Complete Address: Box 486, Ellinwood, KansasLease Name Strait Well No. # 3Location NE SW NW Sec. 33 Twp. 26 Rge. 13 (E) (W) WCounty Pratt Total Depth 4437'Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Pipe Pullers, Inc.Address: Box 486, Ellinwood, Kansas License No. 462Operation Completed: Hour 2:45PM Day 7th Month July Year 1966

The Above well was plugged as follows:

808' of 8 5/8" surface pipe, cemented with 500 sacks. 4429' of 5 1/2" long string,
cemented with 185 sacks. Plug back T.D. 4358'. Top perforation 3812. Bottom
plug and 50' of sand to 3800', and cemented with 5 sacks, through the dump
bailer. 3177' of 5 1/2" long string was recovered from the hole. Bridge plug was
pushed in fluid to 325', rock bridge from 325' to 315'. 8 sacks of cement was
mixed in a barrel, and put on plug at 315', through the dump bailer, and let
set for days. Hole was bailed dry and 25 sacks of cement was added to the plug.
Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with
10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving

Well Plugging Supervisor

DATE 7-8-66INV. NO. 3536-42