

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 6 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Dundee Pipe & Supply

Complete Address Box 2391 Tulsa, OK

Lease Name Galbeck Well No. 4

Location NE/NW/NE Sec. 33 Twp. 26 Rge. 13 (E) W

County Pratt Total Depth 4415

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Co Inc

Address Box 1182 Great Bend, KS License No. 623

Operation Completed: Hour 10:00 AM Day 2 Month 8 Year 1973

The above well was plugged as follows:

799 ft 8 5/8 surface cemented with 600 sacks. 4407 ft 5 1/2 long string
cemented with 250 sacks. Push plug to 4000 ft. Sand & 5 sacks
cement with bailer. Pulled 2300 ft 5 1/2. Set 10 ft rock bridge at
250 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 8/8/73
INV. NO. 7734-u