

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

9-4-73

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
SEP 4 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dundee Pipe & Supply

Complete Address Box 2391 Tulsa, OK

Lease Name Calbeck Well No. 3

Location NE/SW/NE Sec. 33 Twp. 26 Rge. 13 (E) (W)

County Pratt Total Depth 4422

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling Co Inc

Address Box 1182 Great Bend, KS License No. 623

Operation Completed: Hour 10:00 AM Day 30 Month 8 Year 1973

The above well was plugged as follows:

768 ft 8 5/8 surface cemented with 400 sacks. 4412 ft 5 1/2 long string
cemented with 250 sacks. Top perf. 4220 ft. Sand to 4000 ft, 5
sacks cement with bailer. Pulled 3100 ft 5 1/2. Set 10 ft rock bridge
at 250 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 9-4-73
INV. NO. 7871-12