

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

SEP 19 1973

CONSERVATION DIVISION  
Wichita, Kansas  
9-19-73

Operator's Full Name Dundee Pipe & Supply

Complete Address Box 2391 Tulsa, OK

Lease Name Galbeck Well No. 5

Location SW/NE/NE Sec. 33 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4414

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Russ Casing Pulling Co Inc

Address Box 1182 Great Bend, KS License No. 623

Operation Completed: Hour 9:00 AM Day 18 Month 9 Year 1973

The above well was plugged as follows:

796 ft 8 5/8 surface cemented with 400 sacks. 4399 ft 5 1/2 long string  
cemented with 180 sacks. Top perf. 4228 ft. Sand to 4000 ft, 5 sacks  
cement with bailer. Pulled 3120 ft 5 1/2. Set 10 ft rock bridge at  
250 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: M. Russell Bikerstein  
Well Plugging Supervisor

INVOICED

DATE 9-19-73

INV. NO. 7928-10