

15-151-10826-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 6 1973  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Dundee Pipe & Supply  
Complete Address Box 2391 Tulsa, OK  
Lease Name Galbeck Well No. 11  
Location NW/NE/NE Sec. 33 Twp. 26 Rge. 13 (E) (W) W  
County Pratt Total Depth 4455  
Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated       
Plugging Contractor Russ Gasing Pulling Co Inc  
Address Box 1182 Great Bend, KS License No. 623  
Operation Completed: Hour 9:00 AM Day 2 Month 8 Year 1973

The above well was plugged as follows:

215 ft 13" surface cemented with 400 sacks. 906 ft 8 5/8 surface  
cemented with 750 sacks. 4455 ft 5 1/2 long string cemented with 250  
sacks. Push plug to 4000 ft. Sand & 5 sacks cement with bailer.  
Pulled 3100 ft 5 1/2. Set 10 ft rock bridge at 250 ft. Fill hole with  
4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 8/8/73  
INV. NO. 7735-U